

Product Specification Clause

Amicus Altus LAHP-260HTR290 Air to Water Heat Pump

Lochinvar Ltd 8 Lombard Way The MXL Centre, Banbury Oxon, OX16 4TJ

+44 (0) 1295 269981 info@lochinvar.ltd.uk www.lochinvar.ltd.uk

| Description | Unit | Specification | Notes |
|--|-------|---------------|-----------------------------------|
| Design external air temperature | °C | 0 | Change for project requirements |
| Design flow temperature | °C | 65 | Change for project requirements |
| Output at design temperatures | kW | 266.4 | Change for project requirements |
| Minimum external operating temperature | °C | -20 | |
| Number of heat pumps in the cascade | | 4 | |
| Cascade downturn | Ratio | 4:1 | |
| Compressor downturn | Ratio | 8:1 | |
| Maximum flow temperature | °C | 70 | |
| SCOP at 35°C flow | | 3.95 | Average weather conditions |
| SCOP at 55°C flow | | 3.32 | Average weather conditions |
| SCOP at 65°C flow | | 2.5 | Average weather conditions |
| Refrigerant GWP | | <u><</u> 3 | Ultra low GWP natural refrigerant |
| Refrigerant ODP | | 0 | |
| Refrigerant leak detection | | Yes | |
| Double refrigerant safety valves | | Yes | |
| Stainless steel user heat exchanger with flow switch | | Yes | |
| Antifreeze kit | | Yes | |
| Refrigerant pressure gauges | | Yes | |
| Crane lifting hooks | | Yes | |
| Built in primary pump | | Yes | |
| Cascade pipework header kit to rear | | Yes | |
| Cascade control featuring | | Yes | |
| o BMS Fault signal | | Yes | |
| o BMS on/off | | Yes | |
| o Hot water priority | | Yes | |
| o Direct weather compensation | | Yes | |



WEEE Producer Registration Number – WEE/MM6751AA Comply Direct Membership Number – CD01/01363

Registered office: One New Change, London EC4M 9AF | Registered number: 3453820