AMICUS BOOST INSTALLATION PLANNING GUIDE





| Document Control | | | | | |
|-----------------------------|----------|------------------|-------------|--|--|
| Article | Language | Version | Modified by | | |
| Amicus Boost Planning guide | English | V1 November 2022 | S Addis | | |

| Introduction | 4 |
|--|----|
| General | 5 |
| Technical details | 6 |
| Position on site | 7 |
| Positioning multiple units | 7 |
| Sound power data | 8 |
| Pipework sizing and flow rates | 9 |
| Buffer vessel sizing | 9 |
| DHW Supply | 9 |
| Electrical Connections | 10 |
| Standard installation schematics | 11 |
| Drawing 8, Amicus Boost supplying heating and domestic hot water | 12 |
| Installation assistance | 13 |

Introduction

This document includes all the basic information required for the Design team from stage 2 to stage 5 of the project.

The Lochinvar Amicus High temperature water source heat pump range has been designed to provide heating and DHW and can work at temperatures up to 78°. There are 10 models in the range with outputs ranging from 62 to 495kW at standard rating conditions Source water 30/35°C and user water 65/60°C. The individual technical product submittal for each heat pump supplies detailed data on outputs ranging from 10°C source to 78°C user flow.

Each heat pump has the following standard features:

The compressors used are a high-performance scroll type that incorporates a special scroll design which enhances the efficiency of the refrigerant cycle when the source temperature is low. The compressors are all supplied with a crankcase heater and thermal overload protection by a klixon embedded in the motor winding. They are mounted in a separate enclosure thus enabling them to be maintained even if the unit is operating. Access to this enclosure is via the front panel of the unit. The crankcase heater is always powered when the compressor is in stand-by.

On models 302-1402 the compressors are mounted in a special floating frame arrangement, isolating the compressors from the main casing further reducing noise and vibration. The floating frame arrangement typically reduces noise by up to 10dBa.

Source heat exchanger is made from brazed 316 stainless steel.

User heat exchanger made from brazed 316 stainless steel.

Control panel.


General

The Amicus boost heat pump should be sited in an area which:

- Can bear the weight of the unit.
- Has enough space around the unit to allow maintenance, see table 2.
- Does not present a noise nuisance to users of the building and neighbours.

Operational limits

Amicus high temperature heat pumps can provide heating and/or domestic hot water at temperatures up to 78°C. The diagram below shows the general working limits and should be crossed reference with the data shown in the individual model Technical Product Submittal as each is slightly different.



Drawing 1 operational limits


Sizing


When sizing the boost heat pump careful consideration needs to be taken of the source water temperature and what is supplying the source water. Lochinvar can help with sizing your project, contact your local area sales manager or email info@lochinvar.ltd.uk

Technical details

Table 1.1 Dimensions and weights models 302-1402

| Legend | Data | Unit | Model (LAHP WW) | | | | | | |
|--------|--------|------|-----------------|-------------|-------------|-------------|-------------|--------------|--------------|
| | | | LAHP302WWXL | LAHP402WWXL | LAHP602WWXL | LAHP702WWXL | LAHP902WWXL | LAHP1202WWXL | LAHP1402WWXL |
| Α | Height | mm | 1631 | 1631 | 1631 | 1631 | 1631 | 1631 | 1631 |
| В | Width | mm | 790 | 790 | 790 | 790 | 790 | 790 | 790 |
| С | Depth | mm | 1154 | 1154 | 1154 | 1154 | 1154 | 1154 | 1154 |
| We | ight | Kg | 660 | 680 | 700 | 730 | 740 | 760 | 790 |





Drawing 2 Dimensions models 302-1402

Drawing 3 Dimensions models 1804-2604

Table 1.2 Dimensions and weights models 1804-2604

| Legend | Data Unit | | Model (LAHP WW) | | | | | |
|--------|-----------|----|-----------------|-------------|-------------|--|--|--|
| | | | LAHP1804WWS | LAHP2304WWS | LAHP2604WWS | | | |
| Α | Height | mm | 1900 | 1900 | 1900 | | | |
| В | Width | mm | 794 | 794 | 794 | | | |
| С | Depth | mm | 2844 | 2844 | 2844 | | | |
| Wei | ght | Kg | 1320 | 1390 | 1430 | | | |

Full technical details including detailed performance data for each model can be found on the technical product submittal at: https://lochinvar.ltd.uk/amicus-boost-water-source-heat-pumps/


Position on site

Amicus boost heat pumps require minimum clearances around them to enable maintenance of the unit.

The type of model used will impact the required clearances and how multiple units can be laid out.

Table 2 clearances required models 302-1402

| Langua | l lmit | Model | | | | | | | | | |
|--------|--------|-------|------|------|------|------|------|------|--|--|--|
| Legend | Unit | 302 | 402 | 602 | 702 | 902 | 1202 | 1402 | | | |
| А | mm | 1000 | 1000 | 1000 | 1000 | 1000 | 1000 | 1000 | | | |
| В | mm | 500 | 500 | 500 | 500 | 500 | 500 | 500 | | | |
| С | mm | 600 | 600 | 600 | 600 | 600 | 600 | 600 | | | |
| D* | mm | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | | |
| E | mm | 500 | 500 | 500 | 500 | 500 | 500 | 500 | | | |



Drawing 4 Service clearances required models 302-1402

Drawing 5 Service clearances required models 1804-2604

Table 3 clearances required models 302-1402

| | | Model | | | | |
|--------|------|-------|------|------|--|--|
| Legend | Unit | 1804 | 2304 | 2604 | | |
| А | mm | 1000 | 1000 | 1000 | | |
| В | mm | 500 | 500 | 500 | | |
| С | mm | 800 | 800 | 800 | | |
| D | mm | 1000 | 1000 | 1000 | | |
| E | mm | 500 | 500 | 500 | | |

Positioning multiple units

When positioning multiple Amicus units' minimum distances must be observed according to model size to ensure uninterrupted service access, as per table 1 and 2. If plantroom space is tight, please contact Lochinvar technical support for further help and guidance.

Sound power data

Table 4 Sound power levels for standard units

| | octave bands (hz) | | | | | | | | | | |
|------------|-------------------|------|------|------|------|------|------|------|-------|----|----|
| model | 63 | 125 | 250 | 500 | 1k | 2k | 4k | 8k | lw | | lp |
| | db | db | db | db | db | db | db | db | db | db | db |
| LAHP302WW | 78.1 | 69.3 | 63.2 | 61.7 | 60.6 | 55.2 | 51.8 | 42.7 | 78.9 | 65 | 49 |
| LAHP402WW | 78.1 | 69.3 | 63.2 | 61.7 | 60.6 | 55.2 | 51.8 | 42.7 | 78.9 | 65 | 49 |
| LAHP602WW | 83.1 | 74.3 | 68.2 | 66.7 | 65.6 | 60.2 | 56.8 | 47.7 | 83.9 | 70 | 54 |
| LAHP702WW | 86.1 | 77.3 | 71.2 | 68.7 | 68.6 | 63.2 | 59.8 | 50.7 | 86.9 | 73 | 57 |
| LAHP902WW | 87.1 | 78.3 | 72.2 | 70.7 | 69.6 | 64.2 | 60.8 | 51.7 | 87.9 | 74 | 58 |
| LAHP1202WW | 89.1 | 80.3 | 74.2 | 72.7 | 71.6 | 66.2 | 62.8 | 53.7 | 89.9 | 76 | 60 |
| LAHP1402WW | 91.1 | 82.3 | 76.2 | 74.7 | 73.6 | 68.2 | 64.8 | 55.7 | 91.9 | 78 | 62 |
| LAHP1804WW | 101.1 | 92.3 | 86.2 | 84.7 | 83.6 | 78.2 | 74.8 | 65.7 | 101.9 | 88 | 72 |
| LAHP2304WW | 102.1 | 93.3 | 87.2 | 85.7 | 84.6 | 79.2 | 75.8 | 66.7 | 102.9 | 89 | 73 |
| LAHP2604WW | 104.1 | 95.3 | 89.2 | 87.7 | 86.6 | 81.2 | 77.8 | 68.7 | 104.9 | 91 | 75 |

Lw: Sound power level according to ISO 9614

Lp: Sound pressure level measured at 10 metres from the unit in free field conditions direction factor Q=2 to ISO 9614

Pipework sizing and flow rates

Pipework should always be sized to match the flow rates below and maintaining a 5k delta T, this will result in larger pipework compared to a traditional 20k system design. The boost heat pump will require two pumps per unit, a source primary pump and a user primary pump, Lochinvar can supply a suitably sized single head pump for each side of the unit, or an alternative can be specified by the installer.



A suitable flow setter must be fitted to every Amicus unit installed to set the correct flow rate at commissioning.

Design flow rates

Design flow rates can be found on the heat pump individual Technical Product Submittal available from https://lochinvar.ltd.uk/amicus-boost-water-source-heat-pumps/

Buffer vessel sizing

Amicus boost heat pumps require a certain amount of both source volume and system volume to ensure problem free running and to reduce the number of starts and hence wear and tear on the compressor. In practise in most installations a buffer vessel will be required. The minimum system volume will:

- 1. Prevent the unit from running out of source water
- 2. Prevent the unit cycling during low demand.

Minimum water content required.

Minimum water content can be found on the heat pump individual Technical Product Submittal available from https://lochinvar.ltd.uk/amicus-boost-water-source-heat-pumps/

Lochinvar will offer two suitably sized buffer vessels with every Boost heat pump quoted, a source buffer sized on the heat requirements of the Boost unit and the source heat, and a user buffer based on the heat output of the Boost.

DHW Supply

Amicus boost heat pumps can supply low temperature hot water at up to 78°C so are suitable for supplying domestic hot water, even if a pasteurisation of 70°C is required. Domestic hot water can be supplied via a plate and buffer arrangement or with a more traditional indirect vessel. This will depend on the system being supplied and whether the Boost unit is also supplying heating.

Electrical Connections

All models require a 3-phase supply with standard electrical requirements as per table 5.1 and 5.2

Table 5.1 electrical requirements models 302-1402

| • | | | | | | | | |
|---|---------|-----------|-----------|-----------|-----------|-----------|------------|------------|
| | | | Model | | | | | |
| ELECTRICAL DATA | Unit | LAHP302WW | LAHP402WW | LAHP602WW | LAHP702WW | LAHP902WW | LAHP1202WW | LAHP1402WW |
| Nominal voltage supply | Ph/V/Hz | 3/400/50 | 3/400/50 | 3/400/50 | 3/400/50 | 3/400/50 | 3/400/50 | 3/400/50 |
| Maximum voltage supply | V | 430 | 430 | 430 | 430 | 430 | 430 | 430 |
| Minimum voltage supply | V | 380 | 380 | 380 | 380 | 380 | 380 | 380 |
| Maximum input power | kW | 18.3 | 19.4 | 29.9 | 36.6 | 47.8 | 59.6 | 71.6 |
| Maximum input current | Α | 32.8 | 35.4 | 54.2 | 68.6 | 85.8 | 106 | 126 |
| Maximum peak current | Α | 111 | 129 | 167 | 208 | 268 | 325 | 373 |
| Maximum peak current (with soft start fitted) | Α | 73 | 73 | 119 | 136 | 178 | 216 | 249 |
| Input power in stand-by mode | kW | 0.02 | 0.02 | 0.02 | 0.02 | 0.02 | 0.02 | 0.02 |
| Power factor | | 0.78 | 0.82 | 0.81 | 0.75 | 0.9 | 0.83 | 0.88 |

Table 5.2 electrical requirements models 1804-2604

| | | Model | | | | |
|---|---------|------------|------------|------------|--|--|
| ELECTRICAL DATA | Unit | LAHP1804WW | LAHP2304WW | LAHP2604WW | | |
| Nominal voltage supply | Ph/V/Hz | 3/400/50 | 3/400/50 | 3/400/50 | | |
| Maximum voltage supply | V | 430 | 430 | 430 | | |
| Minimum voltage supply | V | 380 | 380 | 380 | | |
| Maximum input power | kW | 95.6 | 119 | 143 | | |
| Maximum input current | Α | 172 | 211 | 252 | | |
| Maximum peak current | Α | 354 | 430 | 499 | | |
| Maximum peak current (with soft start fitted) | Α | 264 | 322 | 375 | | |
| Input power in stand-by mode | kW | 0.02 | 0.02 | 0.02 | | |
| Power factor | | 0.89 | 0.83 | 0.88 | | |

Provision should be made for local isolation with a lockable isolator fitted on or very close to the heat pump. A single 230v plug socket should also be fitted close to the unit to aid commissioning and future maintenance.

Standard electrical connections available


| Standard electrical connections | | | | | |
|---------------------------------|---|--|--|--|--|
| Connection | Note | | | | |
| BTI sensor | Monitor's temperature in the buffer vessel | | | | |
| BTs sensor | Monitor's temperature in the DHW vessel | | | | |
| Source Primary pump | Fitted within the plantroom | | | | |
| User Primary pump | Fitted within the plantroom | | | | |
| DHW Primary pump | Fitted between the heat pump plate and DHW storage vessel | | | | |
| Remote on/off | | | | | |
| Summer/winter mode | Switches to DHW only in summer | | | | |
| Hot water priority | | | | | |
| General alarm | | | | | |
| 3-way valve | Switches between heating and DHW | | | | |

Electrical ancillaries available


- 1. Cascade control, this will be supplied as standard on projects with more than one heat pump.
- 2. Soft start, this reduces the peak Amps at start-up as shown in table 5.1 and 5.2.

Standard installation schematics


This section contains various standard schematics showing the concept installation options for the Amicus range. These drawings must not be used for detailed design but can be built upon by the design team to produce their own installations drawings. Lochinvar does not provide detailed installation drawings but can review any produced by the design team.



Drawing 6, Amicus Boost unit supplying domestic hot water only



Drawing 7, Amicus Boost supplying heating only



Drawing 8, Amicus Boost supplying heating and domestic hot water

Installation assistance

Included in the cost of every Amicus unit is the use of the Lochinvar Project Engineer and commissioning. This helps ensure the units are installed correctly and the end user has the assurance the unit has been commissioned by the manufacturer. After orders are placed a Project Engineer will contact the installer and offer:

- 1. Initial pre-start visit to ensure the installer has all the required information to install the units and has the Project Engineer contact details for telephone and email support during the construction phase.
 - a. This visit covers flow rates, Location of equipment, wiring/controls, integration with other equipment and any other questions the installers may have.
- 2. A second visit during installation to make sure everything is OK.
 - a. This visit will review the progress and check everything is going ok, answer any further questions relating to the install – at this stage it is also good to meet the controls/BMS team.
- 3. A pre-commissioning visit to ensure all installation work is complete prior to the Lochinvar commissioning engineer visit.
 - a. On this visit we will complete the pre-com sheet ensure all works are complete and plan in a commissioning date.
- 4. Commissioning visit

On completion of the commissioning the installer will receive a detailed report.

Notes

Back page





8 Lombard Way, The MXL Centre, Banbury, Oxon, OX16 4TJ
Tel: +44(0) 1295 269 981, Fax: +44(0) 1295 271 640, Email: info@lochinvar.ltd.uk
www.lochinvar.ltd.uk